

SCHEDULE B – PLANS TO BE SUBMITTED FOR APPROVAL AS APPROVED PLANS

Environmental Protection and Environmental Management Plans

Adaptive Management Plan – A plan that provides detailed descriptions of procedures and actions that will be employed should negative effects on the environment be observed. The plan should demonstrate that actions can be taken prior to causing unacceptable effects.

Emergency Response & Health and Safety Plan – A plan that provides details procedures and responsibilities for response to emergency situations that may be encountered.

Environmental Monitoring, Surveillance and Reporting Plan – A plan that describes methods and techniques for collecting and reporting monitoring information regarding environmental conditions at the Undertaking, as well as quantitative thresholds which trigger the implementation of adaptive management strategies.

Explosives Management Plan – A plan, based on best management practices, that describes the methods and techniques used to reduce and control ammonia losses to the environment.

Hazardous Materials Management Plan – A plan that provides details of the storage and handling of various hazardous chemicals utilized in the Undertaking.

Heritage Resource Protection Plan – A plan that describes measures to identify and protect historic sites, historic objects, and works of archaeological, paleontological, pre-historic, historic, scientific or aesthetic value.

Sediment and Erosion Control Plan – A plan that describes methods and techniques for protecting undisturbed lands, minimizing mining footprints and reducing erosion of soils due to land disturbance and weathering by wind and water.

Spill Contingency Plan – A plan that describes the measures designed to minimize the potential impact to the environment following a fuel or chemical spill.

Reclamation and Closure Plan – A plan that details the activities to be undertaken during a period of temporary closure and activities to be undertaken to reclaim the site during and after development and production, including identifying closure objectives, planned progressive reclamation, final closure actions and post closure monitoring and maintenance.

Waste Management Plan – A plan that describes the mitigations and methods used to manage solid and liquid wastes and special wastes to ensure protection of the environment and human health.

Wildlife Protection Plan – A plan that describes the mitigation measures or practices pertaining to wildlife attractants, vehicle use, habitat management, wildlife harassment and wildlife health.

Operations Plans

Mill Operations Plan – A plan that details the activities for the operation and monitoring of the mill.

Mine Development and Operations Plan – A plan that details the activities for the construction, operation, maintenance and monitoring of the mine, including both underground and surface mining activities.

Tailings Management Plan – A plan that describes the activities for the design, construction and operation of facilities for the transport and storage of tailings, including operations, maintenance and surveillance protocols for these facilities.

Waste Rock and Overburden Management Plan – A plan that provides a description of the activities for the segregation of the various overburden and waste rock streams, including how the categories of waste rock will be managed throughout the mine life, details of the construction, operation and monitoring of the various waste rock and overburden storage facilities.